



**PATHFINDER IMPROVEMENTS 2024
BID NO 2023-2024-016**

ADDENDUM NO. 1

16 MAY 2024

ISSUED TO ALL BID DOCUMENT HOLDERS OF RECORD:

Bidders are instructed to read and note the following described changes, corrections, clarifications, omissions, deletions, additions, approvals, and statements pertinent to the Contract Bid and Construction Documents. The original Contract Documents and Specifications remain in full force and effect, except as modified by the following, which shall take precedence over any contrary provisions in the prior documents.

This addendum forms a part of the Contract Documents and modifies the previously issued Drawings and Specification Sections.

I. Addendum Acknowledgement:

The Addendum Acknowledgement, included at the back of this Addendum, must be signed and returned with your bid proposal. Failure to return this form acknowledging receipt of the addendum shall be grounds to reject the bid proposal.

II. Specifications:

A. PROJECT SPECIFICATIONS

1. No modifications in this addendum.

III. Project Plans:

A. SHEET 4

1. Modification of Pay Item 9. S5(PG 64-22 OK) used in place of S4(PG 64-22 OK).
2. Modification of Pay Item 10. S5(PG 64-22 OK) used in place of S4(PG 64-22 OK).
3. Pay Item Note 18 added.

IV. Clarifications:

- A. No clarifications in this addendum.

(Sign Addendum Acknowledgement on next page and turn in with Bid Proposal)

**PATHFINDER IMPROVEMENTS 2024
BID NO 2023-2024-016**

ADDENDUM NO. 1

16 MAY 2024

ADDENDUM ACKNOWLEDGEMENT

The undersigned acknowledges receipt of Addendum No. 1, and the bid submitted is in accordance as set forth herein.

Name of Bidder

By: _____

Date: _____

PAY QUANTITIES					
PATHFINDER IMPROVEMENTS 2024					
PAY ITEM	ODOT SPEC	DESCRIPTION	NOTES	UNIT	QUANTITY
1	201(B)	SELECTIVE CLEARING	1	LSUM	1.00
2	202(A)	UNCLASSIFIED EXCAVATION	2, 3	CY	50.00
3	202(D)	UNCLASSIFIED BORROW	2	CY	50.00
4	221(B)	TEMPORARY SILT FENCE	4	LF	200.00
5	221(E)	TEMPORARY SILT DIKE	4	LF	100.00
6	230(A)	SOLID SLAB SODDING	5	SY	209.00
7	303(A)	AGGREGATE BASE TYPE A	6	CY	1,105.00
8	310(B)	SUBGRADE, METHOD B		SY	6,913.00
9	411(C)	SUPERPAVE, TYPE 55 (PG64-220K)	16, 18	TON	1,467.00
10	411(C)	SUPERPAVE, TYPE 55 (PG64-220K)(LEVELING)	7, 8, 16	TON	135.00
11	412	COLD MILLING PAVEMENT	9	SY	476.00
12	501(A)	STRUCTURAL EXCAVATION (UNCLASSIFIED)	10, 11	CY	2,693.00
13	509(A)	CLASS AA CONCRETE	10	CY	215.00
14	511(A)	REINFORCING STEEL	10	LB	34,400.00
15	601(B)	TYPE I PLAIN RIPRAP WITH FILTER BLANKET		TON	237.00
16	610(A)	CONCRETE SIDEWALK	12	SY	24.00
17	610(I)	TACTILE WARNING DEVICE		SF	24.00
18	612(A)	MANHOLE ADJUST TO GRADE		EA	1.00
19	613(A)	REINFORCED CONCRETE PIPE, ROUND 12" DIA.		LF	96.00
20	613(M)	CULVERT END TREATMENT, SPECIAL		EA	12.00
21	619(A)	REMOVAL OF STRUCTURES AND OBSTRUCTIONS		LSUM	1.00
22	619(B)	REMOVAL OF FENCE		LF	682.00
23	619(B)	REMOVAL OF TRAIL PAVEMENT	13	SY	6,913.00
24	624(E)	FENCE, STYLE CLF 6' HIGH	17	LF	682.00
25	641(A)	MOBILIZATION		LSUM	1.00
26	642(B)	CONSTRUCTION STAKING LEVEL II		LSUM	1.00
27	854(A)	TRAFFIC STRIPE PAINT 4" WIDE	14, 15	LF	700.00
28	880(I)	CONSTRUCTION TRAFFIC CONTROL		LSUM	1.00

PAY ITEM NOTES

- THIS PAY ITEM INCLUDES COMPENSATION FOR REMOVAL OF ALL TREES OR PORTIONS OF TREES IN CONFLICT WITH CONSTRUCTION ACTIVITIES. CONTRACTOR SHALL IDENTIFY LIMBS OR TREES IN CONFLICT WITH CONSTRUCTION ACTIVITIES AND PROVIDE A REMOVAL OR TRIMMING PLAN FOR ENGINEER APPROVAL. CONTRACTOR SHALL NOT TRIM OR REMOVE ANY TREE WITHOUT APPROVAL FROM THE ENGINEER.
- QUANTITY INCLUDES 50 CY TO BE USED AT THE ENGINEER'S DISCRETION.
- EXCAVATION OF UNSUITABLE SUBGRADE SHALL BE PAID UNDER THIS PAY ITEM. CONTRACTOR SHALL NOT REMOVE SUBGRADE MATERIAL WITHOUT PRIOR APPROVAL BY THE ENGINEER. ANY QUANTITY REMOVED WITHOUT APPROVAL OF THE ENGINEER IS DONE AT RISK TO THE CONTRACTOR.
- QUANTITY INCLUDES 100 LF TO BE USED AT THE ENGINEER'S DISCRETION.
- SODDING LOCATIONS TO BE DETERMINED BY THE CITY.
- INCLUDES COST OF SEPARATOR FABRIC.
- THIS ITEM SHALL BE USED IN PLACE OF PAY ITEM 6 IN AREAS WHERE EXISTING ROOTS OR OTHER PAVEMENT SURFACE ABNORMALITIES CAUSE ASPHALT TO BE PLACED IN SEPARATE LIFTS, AS SHOWN IN TYPICAL SECTION IV.
- PAYMENT FOR THIS PAY ITEM INCLUDES APPLICATION OF TACK COAT IN ACCORDANCE WITH ODOT SPECIFICATION 407.
- THIS PAY ITEM IS TO BE USED FOR PROFILE MILLING, ELIMINATING AS MUCH EXISTING ASPHALT OVER ROOTS OR OTHER SURFACE IMPERFECTIONS AS POSSIBLE WITHOUT DAMAGING THE ROOTS OR OTHER UNDERLYING FEATURES.
- PAY PLAN QUANTITY.
- THIS PAY ITEM COMPENSATES THE CONTRACTOR FOR REMOVAL OF ALL EXISTING MATERIALS, EXCLUDING PIPE OR PIPE REMNANTS, NECESSARY TO CONSTRUCT THE DRAINAGE STRUCTURE.
- THIS PAY ITEM IS USED TO COMPENSATE FOR THE PLACEMENT OF AN ADA COMPLIANT RAMP-STREET ENTRANCE.
- THIS PAY ITEM INCLUDES REMOVAL OF ANY AGGREGATE BASE OR SUBGRADE MATERIAL REQUIRED FOR PLACEMENT OF THE TYPICAL SECTION IDENTIFIED FOR THAT SECTION OF THE PLANS.
- INCLUDED IN THIS ITEM IS ADVANCED WARNING SIGNAGE INDICATING THE TRAIL CLOSURES AT THE CLOSEST TRAIL ACCESS POINT AND AT THE POINT OF CLOSURE, COINCIDING WITH THE LIMITS OF CONSTRUCTION.
- CONSTRUCTION SIGNING SHALL BE INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MUTCD, CURRENT EDITION, AND ALL APPLICABLE ODOT STANDARD DRAWINGS. CONTRACTOR SHALL PROVIDE A PROPOSED TRAFFIC CONTROL PLAN FOR APPROVAL BY THE CITY ENGINEER PRIOR TO BEGINNING WORK. AMOUNT BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE, AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTING TRAFFIC CONTROL DEVICES, PAVEMENT MARKINGS, AND FLAGGING ACTIVITIES REQUIRED FOR THE COMPLETION OF THE PROJECT.
- CONTRACTOR SHALL PLACE TACK COAT IN ACCORDANCE WITH ODOT SPECIFICATION 407 ON ANY SURFACE THAT IS TO BE OVERLAID IN WHICH THE EXISTING SURFACE IS IN EXCESS OF 7 DAYS OLD. COST TO BE INCLUDED IN PRICE BID FOR OTHER ITEMS OF WORK.
- TOP AND BOTTOM EDGES OF FENCE SHALL HAVE KNUCKLED SELVAGE. TWISTED SELVAGE IS PROHIBITED. SMOOTH WIRE SHALL BE USED IN LIEU OF AND BARBED WIRE IDENTIFIED ON STANDARD RW3-3. FENCE SHALL BE CONSTRUCTED WITH A CONTINUOUS TOP RAIL.
- COST OF SHOULDERING UP WITH TOPSOIL, AS SHOWN IN THE TYPICAL SECTIONS, SHALL BE INCLUDED IN THE PRICE BID FOR THIS PAY ITEM.



ENGINEERING SERVICES

DATE 1/27/24
 DESCRIPTION MODIFICATION TO PAY ITEMS 9, 10, AND ADDITION OF NOTE 14
 BY
 DRAWN BY
 CHECKED BY
 SUB.

PROJECT: PATHFINDER IMPROVEMENTS & ASSESSMENT

NOTES & PAY QUANTITIES (2 OF 2)

PROJECT NUMBER 2021054
 DATE 04/2024

SHEET 4